

# Independent Assessment of Extreme Rainfall Events Conclusions and Recommendations

Great Lakes Water Authority Board of Directors

June 22, 2022

Delivering a better world



## Introductions



Jeffrey Collins collinslegal



Glen T. Daigger, PhD, P.E.

**Principal Investigator** 



Devan Thomas, P.Eng, M. ASCE

**Team Manager** 

#### Independent Panel Members

- Glen T. Daigger, Ph.D., P.E., University of Michigan, Chair
- Paul W. Behnke, P.E., Behnke Pump Technologies, LLC, Pumping Systems
- Jonathan Jones, P.E., P.H., D.WRE, Wright Water Engineers, Flooding. Mr. Jones was supported by Chris Olson, Ph.D., PE.
- Salil Kharkar, P.E., CMRP, DC Water, Senior Technical Advisor to Chief Operating Officer
- Melanie Kueber Watkins, Ph.D., P.E. Michigan Technological University, Flooding and System Modeling
- Johanna Mathieu, Ph.D., University of Michigan, Electrical and Controls

#### Conclusions June 25/26 Rainfall Event

- The intensity of the rainfall far exceeded the designed capacity of the wastewater system and, as a result, some level of both surface flooding and basement backup was unavoidable.
- Operational problems during the storm event likely exacerbated flooding and basement backup:
  - Electrical supply issues at Freud PS prevented all pumps from operating
  - Vacuum priming system problems at Connors Creek PS delayed pump starts
  - Voltage out-of-range at Bluehill PS prevented all storm pumps from operating
- An analysis of risk of basement backup did not show an appreciable reduction in risk should everything had worked as intended.
- Contract limit exceedances that occurred during the June 25/26, 2021 event did not significantly affect basement backup flooding.
- The above suggests that conveyance capacity in the collection system, not pumping, was the primary cause of flood risk and additional pumping capacity would not have appreciably reduced the risk of basement backups. Rather, a strategic assessment of conveyance improvements, inlet controls and in-system storage is warranted



#### Conclusions July 16 Rainfall Event

- While smaller than the June 25/26 event, the intensity of the rainfall exceeded the designed capacity of the wastewater system in some areas and, in those areas, basement backups were reported.
- The Connors Creek PS and Freud PS operated as intended despite some power quality issues at Freud and no surface flooding was observed. Despite this, numerous basement backups were reported in Jefferson Chalmers suggesting local conveyance issues/restrictions may be present.
- Power quality issues at the Bluehill PS delayed the necessary starting of storm pumps which resulted in high water levels in the station and likely surcharge of the local upstream collection system.



### Recommendations Short Term Recommendations (12-18 months)

#### Improve Asset Availability and Reliability

Short Term (approximately 12 to 18 months)			
General (4.1.1)	Take measures to reduce basement backups. Maintain a level of service of at least 14 of 16 storm pumps at Connors Creek and Freud PS and at least 3 of 4 storm pumps at Bluehill PS. Be ready for extreme storms at all times not just when predicted.		
PS (4.1.2)	Conduct tests on vacuum priming system and pump starting at Connors Creek PS to improve system reliability and to provide operator training opportunities. Develop, improve and document operational measures. Regularly use Connors Creek PS in wet weather and maintain the vacuum priming systems after a large storm events to improve system readiness and enhance operator training.		
Electrical Systems (4.1.3)	Transfer power sources to DTE. Provide capability for emergency generators to be connected to any section of the switchgear to enable generators to power any group of pumps. Develop protocols to operate generators at no-load prior to expected events to enable the pumps to be quickly switched to generator power if there is an outage.		
Mechanical Systems (4.1.4)	Make improvements to seal water and vacuum priming systems. Keep the Connors Creek storage gates and relief gates at the CSO Basins in good working order.		



#### Recommendations Medium Term Recommendations (2-5 years)

#### Retrofits to Improve Infrastructure Performance

nately 2 to 5 years)			A PLAN 32 _
Define level of service objectives with respect to flooding and water quality and implications of water quality requirements. Investigate how those objectives have been achieved previously.		MKE 28 MAR 202	SEAL FLUSH TO ADVISE 84 <sup>4</sup> DIA . AVIWA FLANCE
Implement modifications to the "Freud Pump Station Improvements – DRAFT" report prepared by Arcadis/Brown and Caldwell for GLWA project number CS-120 in August 2020		S Saure S	103.5 <sup>°</sup>
Provide for a policy for redundant PS power sources and perform studies to understand existing and potential power source redundancy.		MIS RETROPIT	2 2 2 7 2 6 7 100 10
Implement intake flow conditioning devices at Connors Creek PS and Freud PS wet wells based on testing and recommendations from the February 2018 Clemson Engineering Hydraulics, Inc. study. Also, replace two storm pumps with vertically suspended pumps at Connors Creek PS. Expand and improve the Connors Creek PS seal water system.	\$16M for IFC devices \$19.5M for VS3i pumps	COMMERS CREEK S-W RU	9 102.0 PLANCE O.E BN EXIST DEA TUBE
Operate and inspect IFC devices. Regularly clean the Connors Creek Storm wet well and IFC devices.		- 414 - 414	<u> Μ</u> ρειτες ε
Review existing studies with consideration of flooding and water quality objectives. Conduct additional studies to understand flooding and water quality level of service and optimize system operations using "real-time" data. Consider different operating procedures for extreme storms that maximizes conveyance but may increase CSOs.		BPT, LLC For C	4 4 140.0 <sup>1</sup> BIDDER BELL TO ADVISE DAM. ↓ 1 36.0 <sup>1</sup> EL.55.0 <sup>1</sup> A 30.0 <sup>1</sup> 0.0
	Define level of service objectives with respect to flooding and water quality and implications of water quality requirements. Investigate how those objectives have been achieved previously.         Implement modifications to the "Freud Pump Station Improvements – DRAFT" report prepared by Arcadis/Brown and Caldwell for GLWA project number CS-120 in August 2020         Provide for a policy for redundant PS power sources and perform studies to understand existing and potential power source redundancy.         Implement intake flow conditioning devices at Connors Creek PS and Freud PS wet wells based on testing and recommendations from the February 2018 Clemson Engineering Hydraulics, Inc. study. Also, replace two storm pumps with vertically suspended pumps at Connors Creek PS. Expand and improve the Connors Creek PS seal water system.         Operate and inspect IFC devices. Regularly clean the Connors Creek Storm wet well and IFC devices.         Review existing studies with consideration of flooding and water quality objectives. Conduct additional studies to understand flooding and water quality level of service and optimize system operations using "real-time" data. Consider different operating procedures for extreme storms that maximizes conveyance but may increase CSOs.	nately 2 to 5 years)Define level of service objectives with respect to flooding and water quality and implications of water quality requirements. Investigate how those objectives have been achieved previously.Implement modifications to the "Freud Pump Station Improvements – DRAFT" report prepared by Arcadis/Brown and Caldwell for GLWA project number CS-120 in August 2020Provide for a policy for redundant PS power sources and perform studies to understand existing and potential power source redundancy.Implement intake flow conditioning devices at Connors Creek PS and Freud PS wet wells based on testing and recommendations from the February 2018 Clemson Engineering Hydraulics, Inc. study. Also, replace two storm pumps with vertically suspended pumps at Connors Creek PS. Expand and improve the Connors Creek PS seal water system.\$16M for IFC devicesOperate and inspect IFC devices. Regularly clean the Connors Creek Storm wet well and IFC devices.\$16J for VS3 i pumpsReview existing studies with consideration of flooding and water quality objectives. Conduct additional studies to understand flooding and water quality level of service and optimize system operations using "real-time" data. Consider different operating procedures for extreme storms that maximizes conveyance but may increase CSOs.	Define level of service objectives with respect to flooding and water quality and implications of water quality requirements. Investigate how those objectives have been achieved previously.       1444         Implement modifications to the "Freud Pump Station Improvements – DRAFT" report prepared by Arcadis/Brown and Caldwell for GLWA project number CS-120 in August 2020       1444         Provide for a policy for redundant PS power sources and perform studies to understand existing and potential power source redundancy.       \$16M for IFC devices         Implement intake flow conditioning devices at Connors Creek PS and Freud PS wet wells based on testing and recommendations from the February 2018 Clemson Engineering Hydraulics, Inc. study. Also, replace two storm pumps with vertically suspended pumps at Connors Creek PS. Expand and improve the Connors Creek PS seal water system.       \$16M for IFC devices.         Operate and inspect IFC devices. Regularly clean the Connors Creek Storm wet well and IFC devices.       Stormerstand fooding and water quality objectives. Conduct additional studies to understand flooding and water quality level of service and optimize system operations using "real-time" data. Consider different operating procedures for extreme storms that maximizes conveyance but may increase CSOs.       1490       <



#### Recommendations Long Term Recommendations (> 5 years)

Investigate and Develop Policies to Maximize Level of Service (LOS)

Long Term (more	e than 5 years)	
General (4.3.1)	Consider implementing comprehensive policies and practices that address the frequency and extent of flood losses.	
PS (4.3.2)	Make additional PS modifications at the Connors Creek PS based on performance of medium-term recommendations, including replacing the remaining six storm pumps and constructing access and screening improvements in lieu of building a new pumping station.	
Regional Coordination		
General (4.4)	Foster regional coordination. Various recommendations generally intended to reduce future flood damages and requiring regional coordination to implement.	



#### Recommendations Long Term Recommendations (> 5 years)

General Recommendations Include:

- 1. Evaluate moving to 100-year design storm standard.
- 2. Local governments evaluate purchase of flood-prone properties provided State/Federal funds available.
- 3. Local government public outreach campaign on flood risk and purchasing flood insurance.
- 4. Engage all relevant stakeholders and use triplebottom-line approach to decision-making.
- Consult with others, such as Tulsa, Houston, Denver, Washington, D.C., St. Louis, New York City, Chicago, Toronto.



Investigate and Develop

Policies to Maximize Level of

10

## Recommendations Long Term Recommendations (> 5 years)

Investigate and Develop Policies to Maximize Level of Service (LOS)

Regional Coordination Recommendations Include:

- 1. Develop system-wide understanding of upstream/downstream interactions.
- 2. Leverage FEMA NFIP program to move toward 100-year level of flood protection.
- 3. Local governments update flood maps.
- 4. Coordinated (GLWA and local communities) and on-going public outreach program.
- 5. GLWA and regional partners develop flood data collection program.
- 6. Leverage available federal funding programs.
- 7. Identify regional stormwater and flood plain management leader and GLWA role.
- 8. Develop regional approach to Federal, state, and local legal and regulatory requirements.



#### Recommendations Funding Sources

- To efficiently implement and effectively fund the actions recommended, GLWA should develop an Implementation Plan that includes recommended projects and actions:
  - Matched to specific federal funding opportunities
  - Compliant with and supporting Justice 40 Directive
  - Prioritized and scheduled based on operational requirements, Justice 40 directive, and funding availability.





# **Questions & Answers**

Delivering a better world



**AECOM** Delivering a better world